

Ground Fixed Stepping Stone 1 of 5




Metric Conversion: 100mm/ 4" 145mm/ 5 45/64" 245mm/ 9 41/64" 345mm/ 13 37/64" 640mm/ 25 13/64"

Ground Works Stepping Stone


1. Ex (in 64

Excavate hole below finished installation level (including surfacing) with dimensions of 640mm x 640mm x 345mm.



- 2. To prevent flooding the foundations should be connected to a rainwater drainage system such as a storm drain or soakaway.
- 3. Install drainage inlet centrally in excavated area 145mm from finished ground level. This will allow for a slight fall in the concrete pad to encourage water runoff.

4. Lay a level compacted 100mm granular sub-base over a geo-textile. This will help to spread the load of the concrete installation pad.



640mm

640mm

Ground Fixed

Stepping Stone 2 of 5



Metric Conversion: 100mm/ 8" 600mm/ 23 5/8" 849mm/ 33 27/64"

Ground Works Stepping Stone

- 5. Create timber shuttering on top of compacted sub-base with an internal area of 600mm x 600mm x 100mm.
 - Note finished height to top of shuttering should be 145mm below finished installation level (including surfacing).
 - To ensure shuttering is square, internal diagonal measurements should be ~849mm.
- Install A142 steel reinforcing mesh (or similar) on 50mm plastic or steel supports or "chairs" to hold mesh vertically centred in shuttering area.
- Install the supplied installation studs jig on top of steel mesh and centre between shuttering and affix in place using cable ties (to ensure no movement when concrete is poured).
 - Note threaded studs must be covered when concrete is poured to ensure threads do not get concrete on them.
 - Threads should protrude 30mm from top of shuttering.
- 8. Pour 100mm depth concrete pad and create slight fall to previously fitted drainage inlet.
 - Consider mixing reinforcement fibres in concrete mix predominantly for crack control rather than structural strengthening.
 - Allow to poured concrete pad to cure for 24-72 hours before proceeding to next step.
 - Remove shuttering after 24-72 hours.

